

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-10191-00-00  
Spot: NWSE Sec/Twnshp/Rge: 33-29S-34W  
2001 feet from S Section Line, 2008 feet from E Section Line  
Lease Name: J.D. ADAMS Well #: 1  
County: HASKELL Total Vertical Depth: 5490 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1840		
CIBP		5354		
SURF	8.625	1804		WITH 750 SX CMT
PROD	5.5	5489	0	WITH 675 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/15/2011 12:30 PM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: DICK SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: CIBP @ 5354'. SHOT 5 1/2" CASING & POH. RIH W/TBG & SPOT 15 SX GEL & 50 SX CMT AT 1850'. 50 SX CMT AT 600'. 15 SX CMT AT 40'.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/15/2011 5:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

WELL HAS CIBP @ 5354'. SHOT 5 1/2" CASING AT 1847'. UNABLE TO PULL. PERFORATED 5 1/2" CASING AT 1845'. PUMPED 78 BBL WATER WITH WELL ON VACUUM. SET CIBP @ 1840'. PERFORATED CASING AT 1835'. RIHW/TBG TO 1800' & SPOTTED 100 SX CMT. TAGGED TOC @ 1200'. PERFORATED CASING AT 600' & CIRCULATED 185 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5403	5423		CHESTER
5282	5294		MORROW
5250	5277		MORROW

RECEIVED  
NOV 23 2011  
KCC WICHITA

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA 10 YR RULE\*\* USED 60/40 POZMIX 4% GEL BY GRESSEL OILFIELD SERVICES.

Plugged through: TBG

District: 01

RECEIVED  
NOV 21 2011  
KCC DODGE CITY

Signed

Jack MacLasky  
(TECHNICIAN)

Form CP-73

11/20/11