

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-19212-00-00
Spot: NWSWSWNW Sec/Twnshp/Rge: 10-17S-4E
2983 feet from S Section Line, 4984 feet from E Section Line
Lease Name: MARTIN C Well #: 1
County: MARION Total Vertical Depth: 2376 feet

Operator License No.: 5192
Op Name: SHAWMAR OIL & GAS CO., INC.
Address: 1116 E MAIN PO BOX 9
MARION, KS 66861

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	1745		
COND	13	105		
PROD	5.5	2327		30 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/02/2011 9:00 AM
Plug Co. License No.: 5192 Plug Co. Name: SHAWMAR OIL & GAS CO., INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC REGULATIONS.

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/02/2011 11:45 AM KCC Agent: SHANE JONES

Actual Plugging Report:

11/1/11 SHAWMAR TAGGED SAND @ 2272' AND CAPPED W/5 SX. DYNALOG OUT AND RAN A BOND LOG FROM 400' TO SURFACE. THEY FOUND GOOD CEMENT TO 50' THEN CEMENT BECAME POOR. BENNY W/SHAWMAR WOULD LIKE TO BULLHEAD CEMENT DOWN THE CASING. WE PRESSURED THE CASING UP 120 PSI, AND IT HELD. DYNALOG PERFED @ 250' THRU BOTH THE 5.5" & 7". NO 13" FOUND BUT BACKSIDE OF 7" WASHED OUT. 11/2/11 CONSOLIDATED TIED ON TO CASING AND TRIED TO CIRCULATE UP THE BACKSIDE OF THE 7". CONSOLIDATED PRESSURED UP TO 500 PSI AND WILL BLEED DOWN TO 300 PSI. NO CIRCULATION UP THE BACKSIDE. CONSOLIDATED PUMPED 100 SX 60/40 POS W/4% GEL DOWN THE CASING. THIS WAS AT LEAST 40 SX OVER FILL. SHAWMAR RAN 1" DOWN THE BACKSIDE TO 50'. CONSOLIDATED TIED ON AND WASHED 1" DOWN TO 60' SOLID BOTTOM. CONSOLIDATED BROKE CIRCULATION WITH WATER. THEY THEN SWITCHED TO CEMENT, AND CIRCULATED 125 SX TO SURFACE. TK #31698 FOR 225 SX 60/40 POS W/4% GEL. 11/3/11 I CHECKED TOP PLUG DOWN 4' INSIDE CASING AT SURFACE ON BACKSIDE. SHAWMAR WILL TOP OFF WHEN CUT OFF CASING.

Perfs:


Top	Bot	Thru	Comments
2327	2376	CSG	MISSISSIPPI

Remarks: DENIED TA (10YR RULE)

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED

NOV 15 2011 Form CP-2/3

KCC WICHITA

11/16/11

JK