

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02029-00-00
Spot: NWSENE Sec/Twnshp/Rge: 24-19S-6W
3561 feet from S Section Line, 1026 feet from E Section Line
Lease Name: SPOHN Well #: 1
County: RICE Total Vertical Depth: 3411 feet

Operator License No.: 32081
Op Name: SMOKEY VALLEY RESOURCES, INC.
Address: 6604 TARRYTOWN ST
PARK CITY, KS 67219

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8	198		100 sxs
PROD	5.5	3402	1800	100 sxs

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/08/2011 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/08/2011 1:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:

11/7/11 KELSO DROPPED SAND. THEY TAGGED SAND @ 3327' AND CAPPED W/5 SX. THEY RIPPED CASING @ 1800'. SHUT DOWN @ 2:00 DUE TO WEATHER.
11/8/11 KELSO PULLED CASING TO 850'. COPELAND TIED ON AND BROKE CIRCULATION. THEY SPOTTED 35 SX COMMON W/3% CC. KELSO'S PULLED UP TO 450' AND WAITED 1 HR. KELSO'S RAN SWAB BAR DOWN AND TAGGED PLUG @ 779'. COPELAND TIED BACK ON AND SPOTTED ANOTHER 35 SX COMMON W/3% CC @ 450' KELSO'S PULLED UP TO 250', AND COPELAND TIED BACK ON. THEY CIRCULATED 180 SX TO SURFACE. KELSO'S PULLED THE REST OF THE CASING HOLE STANDING FULL. COPELAND TK #39385 70 SX COMMON W/3% CC AND 180 SX 60/40 POS W/4% GEL. 11/9/11 VIRGIL CLOTHIER CHECKED TOP PLUG FINDING IT AT SURFACE.

Perfs:

Top	Bot	Thru	Comments
3402	3411	OH	

RECEIVED
NOV 15 2011
KCC WICHITA

Remarks: COMMISSION ORDER DKT #12-051 DEADLINE 11/6/11

Plugged through: CSG

District: 02

Signed  (TECHNICIAN)