

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02030-00-00
Spot: NESENE Sec/Twnshp/Rge: 24-19S-6W
3705 feet from S Section Line, 457 feet from E Section Line
Lease Name: SPOHN Well #: 2
County: RICE Total Vertical Depth: 3409 feet

Operator License No.: 32081
Op Name: SMOKEY VALLEY RESOURCES, INC.
Address: 6604 TARRYTOWN ST
PARK CITY, KS 67219

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8	201		140 sxs
PROD	5.5	3403	1279	100 sxs

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/04/2011 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Revd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/04/2011 1:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:

11/3/11 KELSO DROPPED SAND. THEY TAGGED SAND @ 3342' AND CAPPED W/5 SX. THEY RIPPED CASING @ 1279'. 11/4/11 KELSO PULLED CASING TO 850'. COPELAND TIED ON AND BROKE CIRCULATION. THEY SPOTTED 35 SX COMMON W/2% CC. KELSO'S PULLED UP TO 450' AND WAITED 1 HR. KELSO'S RAN SWAB BAR DOWN AND TAGGED PLUG @ 790'. COPELAND TIED BACK ON AND SPOTTED ANOTHER 35 SX COMMON W/2% CC @ 450' KELSO'S PULLED UP TO 250', AND COPELAND TIED BACK ON. THEY CIRCULATED 125SX TO SURFACE. KELSO'S PULLED THE REST OF THE CASING HOLE STANDING FULL. COPELAND TK #39385 70SX COMMON W/2% CC AND 125 SX 60/40 POS W/4% GEL. 11/7/11 I CHECKED TOP PLUG FINDING IT AT SURFACE.

Perfs:


Top	Bot	Thru	Comments
3403	3409	OH	

Remarks: COMMISSION ORDER DKT #12-051 DEADLINE 11/6/11

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

RECEIVED

NOV 15 2011

Form CP-2/3

11/16/11

KCC WICHITA

✓