

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-20701-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 24-21S-4E
5090 feet from S Section Line, 2492 feet from E Section Line
Lease Name: ALLISON Well #: 2
County: MARION Total Vertical Depth: 2432 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200		
PROD	4.5	2432		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/02/2011 1:00 PM
Plug Co. License No.: 3038 Plug Co. Name: CYCLONE WELL SERVICE, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/02/2011 3:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:

CYCLONE DROPPED SAND. THEY TAGGED AT 2334' AND CAPPED W/4 SX CEMENT. THEY ARE NOT PULLING DUE TO RECORDS SHOWING OLD SQUEEZE UP HIGH. THEY RAN TUBING DOWN TO 250'. COPELAND TIED ON AND CIRCULATED CEMENT TO SURFACE WITH 30 SX. CYCLONE THEN RAN 3/4" PIPE DOWN THE BACKSIDE TO 75' WASHED DOWN TO 80' GOOD SOLID BOTTOM. COPELAND TIED ON AND CIRCULATED THE BACKSIDE FULL WITH 15 SX. HOLE STANDING FULL. TK #37821 FOR 45 SX 60/40 POX W/4% GEL. 11/3/11 I CHECHED TOP PLUG FOUND IT DOWN 5' INSIDE CASING AND 1' DOWN ON BACKSIDE. OPERATOR WILL TOP OFF WHEN THEY CUT OFF CASING.

Perfs:


Top	Bot	Thru	Comments
2389	2395	CSG	Meisner

RECEIVED
NOV 15 2011
KCC WICHITA

Remarks: EXPIRED TA 1/26/11 OPERATOR WAS SENT 2 NOTICE OF EXPIRED TA ON NEW CP-111 FILED

Plugged through: TBG

District: 02

Signed  (TECHNICIAN)

11/15/11

JK