

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20295-00-01
Spot: NESWSE Sec/Twnshp/Rge: 23-21S-2W
983 feet from S Section Line, 1646 feet from E Section Line
Lease Name: ORLANDO UNRUH B1 Well #: 1
County: MCPHERSON Total Vertical Depth: 3371 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	150		100 SX
PROD	4.5	3370	1400	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/28/2011 2:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/01/2011 4:30 PM KCC Agent: SHANE JONES

Actual Plugging Report:

KELSO'S TAGGED SAND @ 3280' AND CAPPED W/4 SX. THE RIPPED CASING @ 1400'. THEY PULLED UP TO 420'. COPELAND TIED ON AND SPOTTED 150 SX 60/40 POS W/4%GEL, 2 BAGS HULLS AND 3 SX CC TIK #37814. 10/31/11 I CHECKED TOP PLUG. I FOUND IT DOWN 50', BUT NOT SOLID. 11/1/11 COPELAND OUT AND RAN POLY PIPE DOWN TO 60' AND WASHED ON DOWN TO 100'. COPELAND CIRCULATED 70SX 60/40 POS W/4% GEL TO SURFACE. TK #37818 11/3/11 I CHECKED TOP PLUG AND FOUND IT AT SURFACE.

Perfs:

RECEIVED
NOV 15 2011
KCC WICHITA

Remarks: INACTIVE WELL (LAST PRODUCTION FOR LEASE WAS 2005 AS PER KGS) NO CP-111 ON FILE

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

Form CP-2/3

11/15/11

SK