

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20920-00-00
Spot: NESESW Sec/Twnshp/Rge: 31-17S-3W
870 feet from S Section Line, 2831 feet from E Section Line
Lease Name: PATRICK SWD Well #: 2
County: MCPHERSON Total Vertical Depth: 3508 feet

Operator License No.: 32062
Op Name: ARDC INC.
Address: 108 W 34TH ST
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3350		
SURF	8.625	431		75 SX
COND	10.75	208		200 SX
PROD	5.5	3508	920	150 SX

Well Type: SWD UIC Docket No: D20702.0 Date/Time to Plug: 10/18/2011 10:00 AM

Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/18/2011 10:00 AM KCC Agent: SHANE JONES

Actual Plugging Report:

10/18/11 CREW RAN TUBING IN CAN NOT GET PAST 1422'. DISTRICT OFFICE CONTACTED AND PLUGGING ORDERS GIVEN. PULLING UNIT CREW PULLED 920' OF 5 1/2" CASING. THEY RAN BACK IN WITH TUBING TO 1413' ALLIED PUMPED 35 SX OF COMMON W/3% CC. WAITED 1 HR AND RAN BACK INTO TAG PLUG. DID NOT TAG ANY PLUG. THEY PUMPED ANOTHER 35 SX COMMON W/3% AND 150 LBS HULLS. THEY WAITED 1 HR, STILL DID NOT TAG PLUG. THEY THEN PUMPED 30 SX COMMON AND 150 SX OF 60/40 POS W/3% GEL AND SHUT IN OVER NIGHT. (WITNESSED BY PATRICK SHIELDS) 10/19/2011 I TAGGED PLUG @ 586'. RIG RAN TUBING TO 460', AND ALLIED CIRCULATED 135 SX TO SURFACE. THEY PULLED THE TUBING AND TOPPED OFF WITH 5 SX. ALLIED TK # 038320 60/40 POS W4% GEL. OPERATOR OUT AND TOPPED PLUG TO SURFACE. 11/3/11 I CHECKED TOP PLUG @ SURFACE.

Perfs:


Top	Bot	Thru	Comments
3475	3480	CSG	MAQUOKETO
3079	3099	CSG	MISSISSIPPIAN

RECEIVED
NOV 15 2011
KCC WICHITA

Remarks: FAILED MIT ON 6/21/11. MAQUOKETO PERF 3475 - 3480 PLUGGED BACK TO 3350, DISPOSING IN MISSISSIPPI

Plugged through: TBG

District: 02

Signed  (TECHNICIAN)
cc to WCC 11/15/11
Form CP-2/3
11/15/11