

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-169-20,261-0000

SE/4, Sec. 7, T 16 S, R 1 (W)

330 feet from (S) section line

990 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5120

Lease Name Karber "A" Well # 1

Operator: Range Oil Company, Inc.
Name & Address 240 Page Court
220 W. Douglas
Wichita, Kansas 67202

County Saline

Well Total Depth 2757 feet 89.60

Conductor Pipe: Size feet

Surface Casing: Size 8 3/8 feet 219

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Range Drilling Co, Inc. License Number 5124

Address 240 Page Court, 220 W. Douglas, Wichita, Kansas 67202

Company to plug at: Hour: 8:00 AM Day: 8 Month: October Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Tim Zulkoski

(company name) Range Drilling Co, Inc. (phone) 316 221 6345

were: Fill hole with heavy mud. Pump 50 sacks 60/40 Pozmix
w/2% gel and 3% C.C. through drill pipe @ 275'. Push plug and
1/2 sack hulls to 60' and cement to base of collar with 20
sacks 60/40 Poz. Cement ratihole with 10 sacks cement

Signed Arthur J. Loman
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:30 AM Day: 8 Month: October Year: 1984

ACTUAL PLUGGING REPORT Hole filled with heavy mud. 50 sacks 60/40 Pozmix
w/2% gel and 3% cc pumped through drill pipe @ 275'.
Plug and 1/2 sack hulls pushed to 60' and hole cemented with
20 sacks cement. Rathole cemented with 10 sacks cement.

Remarks: TD-Formation - Mississippi Gh. Elev. 1326'
Halliburton Ticket # 256367

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION
OCT 16 1984
10-16-84
Wichita, Kansas

Signed Arthur J. Loman
(TECHNICIAN)

10-18-84
4404