

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-00635-00-01
Spot: NWNWSWSW Sec/Twnshp/Rge: 6-16S-10W
1042 feet from S Section Line, 4964 feet from E Section Line
Lease Name: BARCLAY Well #: 3
County: ELLSWORTH Total Vertical Depth: 3363 feet

Operator License No.: 31561
Op Name: HOFFMAN, CHRIS DBA C & K OIL COM
Address: 410 B ST PO BOX 531
CLAFLIN, KS 67525

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| SURF | 12 | 485 | | 75 SX |
| PROD | 5.5 | 3343 | | 120 SX |

Well Type: SWD UIC Docket No: E19301.1 Date/Time to Plug: 11/07/2011 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 11/07/2011 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CASING PARTED AT 1900'. GOT DOWN TO 2000' WITH TUBING. PUMPED 50 SX'S COMMON CEMENT WITH CC. PERFORATE AT 1400', 1050', 560', AND 260'. RUN TUBING TO 1400' AND PUMP 50 SX'S COMMON AND CC. PULL TUBING TO 1050' AND PUMP 50 SX'S COMMON AND CC. PULL TUBING TO 560' AND PUMP 50 SX'S COMMON WITH CC. LET SET FOR 1 HR AND TAG AT 490'. PULL TUBING TO 260' AND CIRCULATE CEMENT 60-40 POZ, 4% GEL TO SURFACE. RUN 2" TUBING DOWN BACKSIDE OF 5.5" TO 130'--WHERE STACKED OUT AT, AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP CASINGS OFF. ACCORDING TO SCOUT CARD, WELL HAD OTHER SIZE CASINGS THAT WERE PULLED OUT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3349 | 3363 | OH | ARBUCKLE |

Remarks: COPELAND TICKET C-39362

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

✓ a to MIC 11/18/11

✓

RECEIVED Form CP-2/3
NOV 17 2011 11/28/11

KCC WICHITA