

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21626-00-00
Spot: SWNESW Sec/Twnshp/Rge: 34-34S-5W
1750 feet from S Section Line, 1550 feet from W Section Line
Lease Name: BAKER Well #: 1-34
County: HARPER Total Vertical Depth: 5229 feet

Operator License No.: 31885
Op Name: M & M EXPLORATION, INC.
Address: 4257 MAIN ST., #230
WESTMINSTER, CO 80031

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4688		
SURF	8.625	395		250 SX
T1	2.875	4684		
PROD	5.5	5215	2800	295 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/05/2011 10:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN VRATIL Company: M&M EXPLORATION, INC. Phone: (620) 886-0698

Proposed Plugging Method: AS PER KCC RULES AND REGS

Plugging Proposal Received By: DAN FOX Witness Type: NONE
Date/Time Plugging Completed: 10/05/2011 10:30 AM KCC Agent: DAN FOX

Actual Plugging Report:

CIBP SET @ 4688' CAPPED OFF WITH 2 SX W/DUMP BALER, LAID DOWN 2800' OF 5 1/2" PRODUCTION CASING. RAN TUBING BACK IN @ 975' TO SPOT 35 SX FOR BOTTOM SALT PLUG THEN UP TO 675' AND SPOTTED 35 SX FOR TOP PLUG OF SALT SECTION. THEN RAN UP TO 450' CIRC. TO SURFACE WITH 136 SX.

Perfs:

Top	Bot	Thru	Comments
4983	5030	CSG	
4876	4880	CSG	
4860	4862	CSG	
4845	4852	CSG	
4803	4816	CSG	
4735	4791	CSG	

Remarks: PLUG JOB WAS CALLED IN BY MARK MORGENSTERN W/CLARKE CORP. & RECEIVED BY DAN FOX AT BARREL DESK 10/5/2011 @ 12:00 NOON

Plugged through: TBG

District: 02

Signed Daniel R. Fox

(TECHNICIAN) RECEIVED

NOV 17 2011

Form CP-2/3

KCC WICHITA

11/28/11

JK