

TO: STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-073-23951-00-00  
Spot: NESE Sec/Twnshp/Rge: 23-23S-9E  
1980 feet from S Section Line, 660 feet from E Section Line  
Lease Name: DUNLAP 23-9 Well #: 3  
County: GREENWOOD Total Vertical Depth: 2575 feet

Operator License No.: 34167  
Op Name: FALL RIVER EXPLORATION LLC  
Address: 7416 S GARY PL  
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	209		140 sx
PROD	5.5	2527		140 sx

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/27/2011 8:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: JOHN MITCHELL Company: \_\_\_\_\_ Phone: (918) 494-2734

Proposed Plugging Method: Run tubing to 2040', pump 25 sxs cement; shoot 5 1/2" production casing at 1200' and pull same, run tubing to 1200', pump 25 sx cement @ 1200'; set 250' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed 10/28/2011 1:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 2040' pump 30 sxs cement, shot casing @ 1200' 1100' 850' 597' pumped 30 sxs cement @ 680' pulled casing out 597', ran tubing to 270' pumped 115 sxs cement, gel spacers between cement plugs

Perfs:

Top	Bot	Thru	Comments
2428	2430		SPF
2420	2422		SPF
2393	2396		SPF
2344	2346		SPF
2268	2270		SPF
2233	2236		SPF
2204	2208		SPF
2110	2113		SPF
2102	2106		SPF
2074	2077		SPF
2045	2047		SPF

RECEIVED

MA

KCC Chanute Dist. #3

Remarks:

Plugged through: CSG

District: 03

Signed

Mike Heffern  
(TECHNICIAN)

RECEIVED

Form CP-2/3

NOV 17 2011

11/28/11

KCC WICHITA