

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-20937-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 4-20S-9W
1550 feet from S Section Line, 4998 feet from E Section Line
Lease Name: MCGLYNN Well #: 4
County: RICE Total Vertical Depth: 3575 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	230		175 SX
T1	2.375	3254	340	
PKR	2.375	3254		
PROD	4.5	3400		100 SX

Well Type: SWD UIC Docket No: D20806.0 Date/Time to Plug: 10/28/2011 2:00 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: JOE BURDETT Company: GRESSEL OILFIELD SERVICE, LLC Phone: (620) 960-5612

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/31/2011 10:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

ATTEMPTED TO MIT WELL, WOULDN'T PASS--SO MIRU, ATTEMPT TO PULL TUBING AND PACKER. PULLED TUBING APART. ONLY ABLE TO GET OUT APPROX. 340' OF TUBING, USING FISHING TOOLS. MILLED ON --GOT OUT PIECES, MAKING ONLY 20' IN ONE DAY, DOWN TO 446'. HAD TIGHT SPOT AT 300', SO COULD NOT RUN IN A CIBP. PERFORATE AT 400'. RUN TUBING TO TOP OF TUBING FISH AND ATTEMPTED TO CIRCULATE COMMON CEMENT TO SURFACE. DID NOT GET CEMENT TO CIRCULATE. CAME BACK ON 10-31-11 AND TAGGED CEMENT TOP AT 370'. PUMPED COMMON CEMENT AND CIRCULATED TO SURFACE OUT OF BOTH CASINGS. PULL TUBING OUT AND TOP OFF. WELL PLUGGED AS COMPLIANCE ISSUE--DUE TO NOT BEING CAPABLE OF PASSING MIT.

Perfs:

Top	Bot	Thru	Comments
3400	3575	OH	

Remarks: GRESSELL PERF TICKET #0836. COPELAND CEMENT #C-39358.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

cc to MIC 11/18/11

RECEIVED

NOV 17 2011

Form CP-2/3

11/28/11

KCC WICHITA