

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-00096-00-02  
Spot: W2SESW Sec/Twnshp/Rge: 35-17S-4W  
659 feet from S Section Line, 3647 feet from E Section Line  
Lease Name: SIDNEY JOHNSON TRUST "B" Well #: 1  
County: MCPHERSON Total Vertical Depth: 3705 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	391		
COND	12.5	175		
PROD	5.5	3705		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/31/2011 11:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: JOE BURDETT Company: GRESSEL OILFIELD SERVICES, LL Phone: (620) 960-5612

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/31/2011 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 3410' AND CAP WITH 5 SX'S CEMENT. ATTEMPTED TO PULL CASING--NO STRETCH. PERFORATE AT 500', RUN TUBING TO 500' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. HAD CEMENT ON BACKSIDE OF 5.5" CASING.

Perfs:

Top	Bot	Thru	Comments
3461	3462	CSG	MISNER SAND

Remarks: WELL HAD BEEN DENIED TA STATUS DUE TO HIGH FLUID LEVEL AND CASING LEAK AT 1100'. COPELAND TICKET #C-37816. GRESSEL PERF TICKET #0838

Plugged through: TBG

District: 02

Signed

*Virgil Clothier*

(TECHNICIAN)

RECEIVED

NOV 17 2011

Form CP-2/3

11/28/11

KCC WICHITA

JK