

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-173-00184-00-01
Spot: SESESW Sec/Twnshp/Rge: 18-29S-1E
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: HUFFMAN Well #: 1
County: SEDGWICK Total Vertical Depth: 3329 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	256		120 SX
T1	2.875	3370		
PROD	5.5	3358	1453	80 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/06/2011 11:30 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: JOE BURNETT Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS, SAND BACK 50' ABOVE PERFS. @ 3347' AND CAP W/5 SX, CIBP @ 2850' W/5 SX PULLED PIPE, SET TOP PLUG @ 50' BELOW BOTTOM OF SURFACE CASING AND CIRC TO SURFACE.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/06/2011 11:30 AM KCC Agent: DAN FOX

Actual Plugging Report:

ON OCTOBER 3, 2011 GRESSEL OILFIELD SERVICE MIRU THEN RIH W/WORK STRING, AND BECAUSE OF THE DISTANCE BETWEEN THE TOP OF THE BOTTOM PERFS. TO THE BOTTOM OF THE TOP PERFS WHICH IS ABOUT 480', THE BOTTOM PLUG IS TO BE IN TWO STAGES, GRESSEL RAN IN HOLE 80 GALS OF SAND AND CAPPED WITH 5 SXS. THEN SET A CIBP @ 2850' CAPPED W/5 SX. THEN PULLED 1453' OF PIPE. RAN BACK IN @ 310' AND CIRC. TO SURFACE WITH 120 SX USING A 60/40 POSMIX WITH 4% GEL.

Perfs:

Top	Bot	Thru	Comments
3358	3380	OH	OPEN HOLE
3347	3353	CSG	
2861	2867	CSG	

Remarks: COPELAND ACID AND CEMENT TICKET #37795

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED

Form CP-2/3

NOV 17 2011

11/20/11

KCC WICHITA