

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-00164-00-01
Spot: SESWNE Sec/Twnshp/Rge: 12-33S-3E
3028 feet from S Section Line, 1778 feet from E Section Line
Lease Name: KROTH Well #: 1
County: COWLEY Total Vertical Depth: 3325 feet

Operator License No.: 33405
Op Name: ANSTINE & MUSGROVE INC.
Address: PO BOX 391
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.628	130		CIRCULATED TO SURFACE
PROD	5.5	3323		150 SX

Well Type: EOR UIC Docket No: E15536.5 Date/Time to Plug: 10/25/2011 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/27/2011 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3200', DUMP BAILED 5 SXS CEMENT ON TOP. SHOT SQUEEZE HOLES @ 355'-356'. RIH W/TBG @ 360', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 87 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 10-27-2011 5:00 PM. CONSOLIDATED CEMENT TICKET #31693.

Perfs:


Top	Bot	Thru	Comments
3247	3265	CSG	MISSISSIPPI

Remarks: FAILED MIT

Plugged through: TBG

District: 02

Signed


(TECHNICIAN)

✓ cc to MIC 11/18/11

RECEIVED

Form CP-2/3

NOV 17 2011

✓ 11/28/11

✓

KCC WICHITA