

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-20266-00-01  
Spot: NWNENE Sec/Twnshp/Rge: 12-13S-22W  
4950 feet from S Section Line, 990 feet from E Section Line  
Lease Name: HERL Well #: 1  
County: TREGO Total Vertical Depth: 3896 feet

Operator License No.: 30717  
Op Name: DOWNING-NELSON OIL CO INC  
Address: PO BOX 1019  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	224	0	160 SX
PKR		3715		
PROD	5.5	3896	0	175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/04/2011 8:00 AM  
Plug Co. License No.: 31720 Plug Co. Name: STEWART WELL SERVICE INC  
Proposal Rcvd. from: TERRY W. PIESKER Company: DOWNING-NELSON OIL CO INC. Phone: (785) 735-4363

Proposed Plugging Method: Ordered 600 sxs 60/40 pozmix - 4% gel - 500# hulls to plug with squeeze at 1515' with 900 sxs cement - lost circulation. Junk in the hole at 1976' - can not get down any farther.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/04/2011 10:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

10/17/2011 - TUB to 1875' - pumped 75 sxs cement on strong vacuum - shut down.  
10/18/2011 - Pumped 100 sxs cement with 250# hulls. Set for three hours.  
Pumped 200 sxs cement with 350# hulls on vacuum - moved off - let set.  
11/04/2011 - Moved in - ran tubing - tagged at 565' - pumped 63 sxs cement - good circulation.  
Pulled tubing out - topped off with 5 sxs cement.  
Tied onto backside - pumped 50 sxs cement - full.  
Shut in at 100# P.S.I.

Perfs:

Top	Bot	Thru	Comments
3807	3814		
3785	3791		
3761	3771		
3745	3750		
3726	3730		
3661	3663		
3645	3648		
3623	3628		

RECEIVED  
NOV 18 2011  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #38360.

Plugged through: TBG

District: 04

Signed Marvin Mills  
(TECHNICIAN)

CM

Form CP-2/3

✓ 11/28/11

NOV 08 2011