

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-20444-00-00  
Spot: W2NESW Sec/Twnshp/Rge: 36-30S-34W  
1980 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: UNGLES Well #: 1-36  
County: HASKELL Total Vertical Depth: 5850 feet

Operator License No.: 4951  
Op Name: CLAASSEN OIL AND GAS, INC.  
Address: PO BOX 417  
ESTES PARK, CO 80517

| String | Size  | Depth (ft) | Pulled (ft) | Comment         |
|--------|-------|------------|-------------|-----------------|
| CIBP   |       | 1900       |             |                 |
| CIBP   |       | 5100       |             |                 |
| CIBP   |       | 5280       |             |                 |
| SURF   | 8.625 | 1746       |             | WITH 675 SX CMT |
| COND   | 22    | 30         |             | WITH 6 SX CMT   |
| PROD   | 4.5   | 5600       | 1785        | WITH 325 SX CMT |

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/25/2011 9:00 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SET CIBP @ 5100' & TEST CASING, IF CASING HOLDS, PUMP 50 SX CMT AT 1780', 50 SX CMT AT 630' & 10 SX CMT AT 40'.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/25/2011 3:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 5100', UNABLE TO LOAD CSG. SET CIBP @ 1900' & TESTED CASING TO 500 PSI. HELD OK. 1ST PLUG AT 1780' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 5308 | 5327 |      |          |
| 5290 | 5302 |      |          |
| 5260 | 5263 |      |          |
| 5202 | 5204 |      |          |
| 5159 | 5161 |      |          |
| 5144 | 5148 |      |          |
| 5123 | 5136 |      |          |

RECEIVED  
NOV 18 2011  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD.

Plugged through: CSG

District: 01  
RECEIVED  
OCT 31 2011  
KCC DODGE CITY

Signed Jack MacLaskey  
(TECHNICIAN)

Form CP-2/3  
11/28/11