

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-21532-00-00  
Spot: NWENWSW Sec/Twnshp/Rge: 15-32S-21W  
2714 feet from N Section Line, 688 feet from W Section Line  
Lease Name: STEPHENS Well #: 3  
County: CLARK Total Vertical Depth: 6760 feet

Operator License No.: 31691  
Op Name: CORAL COAST PETROLEUM, L.C.  
Address: 8100 E 22ND ST N BLDG 600, STE R  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	643		WITH 125 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/28/2011 11:00 AM  
Plug Co. License No.: 34233 Plug Co. Name: MAVERICK DRILLING LLC  
Proposal Rcvd. from: CECIL FARMER Company: MAVERICK DRILLING LLC Phone: (316) 262-6700

Proposed Plugging Method: 1ST PLUG AT 6710' WITH 50 SX CMT. 2ND PLUG AT 1080' WITH 50 SX CMT. 3RD PLUG AT 690' WITH 50 SX CMT. 4TH PLUG AT 230' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: NONE  
Date/Time Plugging Completed: 10/28/2011 1:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

Perfs:

1ST PLUG AT 6710' WITH 50 SX CMT. 2ND PLUG AT 1080' WITH 50 SX CMT. 3RD PLUG AT 690' WITH 50 SX CMT. 4TH PLUG AT 230' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

RECEIVED  
NOV 18 2011  
KCC WICHITA

District: 01

Signed

Jack MacLashy  
(TECHNICIAN)

RECEIVED  
NOV - 7 2011  
KCC DODGE CITY

Form C-2011

4/28/11