

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-00850-00-00
Spot: SENESE Sec/Twnshp/Rge: 26-12S-22W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: SCOTT CHAS NCT-1 Well #: 5
County: TREGO Total Vertical Depth: 4040 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	328	0	225 SX
PROD	5.5	4009	0	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/08/2011 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: FRANCIS HITSCHMANN Company: CARMEN SCHMITT, INC. Phone: (620) 793-5100

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls - 15 sxs gel.
DV Tool at 1778' w/400 sxs.

Plugging Proposal Received By: MARVIN MILLS Witness Type: NONE
Date/Time Plugging Completed: 11/08/2011 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3590' - pumped 15 sxs gel - followed with 50 sxs cement and 100# hulls.
Pulled tubing to 1900' - pumped 185 sxs cement - good circulation - pulled tubing out.
Tied onto backside - full - hit P.S.I. 200#
Topped off the casing with 15 sxs cement..

Perfs:

Top	Bot	Thru	Comments
4009	4040		ARBUCKLE (OPEN)

RECEIVED
NOV 18 2011
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING-TICKET #061.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

NOV 08 2011

✓ 11/28/11