

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20061-00-00
Spot: NWSESE Sec/Twnshp/Rge: 26-12S-22W
990 feet from S Section Line, 990 feet from E Section Line
Lease Name: SCOTT C NCT-1 Well #: 6-6
County: TREGO Total Vertical Depth: 4030 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	9.625	313	0	225 SX
PROD 7		3988	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/07/2011 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: FRANCIS HITSCHMANN Company: CARMEN SCHMITT, INC. Phone: (620) 793-5100

Proposed Plugging Method: Ordered 500 sxs 60/40 pozmix - 4% gel - 600# hulls - 27 sxs gel.
DV Tool at 1749' w/325 sxs.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/07/2011 3:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3940' - pumped 27 sxs gel - followed with 85 sxs cement.
Pulled tubing to 1811' - pumped 280 sxs cement with 300# hulls - good circulation of cement.
Pulled tubing out - pumped 25 sxs cement - casing full.
Tied onto backside and pumped 5 sxs cement - full.

Perfs:

Top	Bot	Thru	Comments
3989	4003		ARBUCKLE (OPEN)

RECEIVED
NOV 18 2011
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #112.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

✓ 11/28/11

NOV 07 2011