

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-22538-01-00  
Spot: SESWSWSW Sec/Twnshp/Rge: 27-32S-36W  
150 feet from S Section Line, 455 feet from W Section Line  
Lease Name: SULLINS Well #: 34 2H  
County: STEVENS Total Vertical Depth: 8663 feet

Operator License No.: 5278  
Op Name: EOG RESOURCES, INC.  
Address: 3817 NW EXPRESSWAY STE 500  
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5900		WITH 5 SX CMT
SURF	9.625	1723		WITH 480 SX CMT
	11 7	6370	1850	WITH 160 SX CMT
PROD	4.5	8659	5320	WITH 170 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/20/2011 8:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: TERRY MAXWELL Company: EOG RESOURCES Phone: (405) 246-3252

Proposed Plugging Method: SET CIBP @ 5900' IN 4 1/2" CASING WITH 5 SX CMT. SHOOT 4 1/2" CASING & POH WITH 4 1/2" CASING. SHOOT 7" CASING & POH W/7" CASING. RIH W/TBG TO TOP OFF 7" CASING & SPOT 80 SX CMT. POH TO 1750' & SPOT 60 SX CMT. POH TO 530' & SPOT 50 SX CMT. FILL CASING FROM 60' TO SURFACE.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/25/2011 3:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP IN 4 1/2" CASING AT 5900' WITH 5 SX CMT. SHOT 4 1/2" CASING AT 5320' & POH W/CASING. RIH W/TBG TO 5330' & SPOTTED 80 SX CMT. SHOT 7" CASING AT 1850' & POH W/CASING. RIH W/TBG TO 1755' & PUMPED 100 SX CMT. PUMP 70 SX CMT AT 540'. FILLED CASING FROM 60' TO SURFACE WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6504	8498		MIDDLE MORRO

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

RECEIVED  
NOV 18 2011  
KCC WICHITA

District: 01

Signed

Jack L MacLasky  
(TECHNICIAN)

RECEIVED

OCT 28 2011

KCC DODGE CITY

Form C-20

11/28/11