

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26173-00-00
Spot: NENWSENE Sec/Twnshp/Rge: 18-13S-20W
1620 feet from N Section Line, 940 feet from E Section Line
Lease Name: KOHL Well #: 1-18
County: ELLIS Total Vertical Depth: 3957 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	222		150 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/26/2011 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE
Date/Time Plugging Completed: 10/26/2011 9:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 3889' w/25 sxs.
2nd. Plug at 1556' w/25 sxs.
3rd. Plug at 775' w/100 sxs.
4th. Plug at 270' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

RECEIVED
NOV 23 2011
KCC WICHITA

Form CP-2/3

11/28/11

NOV 16 2011