

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20805-00-01
Spot: NESWSE Sec/Twnshp/Rge: 28-11S-22W
949 feet from S Section Line, 1746 feet from E Section Line
Lease Name: HONAS B Well #: 3
County: TREGO Total Vertical Depth: 4010 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3875		
SURF	8.625	303	0	200 SX
PROD	4.5	4008	0	1000 SX

Well Type: EOR UIC Docket No: E23813.3 Date/Time to Plug: 11/14/2011 10:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: BUTCH Company: CHARTER ENERGY, INC. Phone: (620) 793-9090

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel.
Junk in the hole at 1913'.
Lost tools and tubing in the hole - cannot retrieve - plug from here per Supervisor Case Morris.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/14/2011 12:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 1800' - pumped good circulation of cement with 100 sxs.
Pulled tubing out - tied onto backside - full. Max. P.S.I. 200#.
Tied onto casing - squeezed with 20 sxs cement. S.I.P. 1800#.

Perfs:

Top	Bot	Thru	Comments
3914	3928		MARMATON
3620	3625		LANSING

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #525.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

CM

✓ cc to MIC 11/23/11

Form CP-2/3

✓ 11/23/11

NOV 18 2011

RECEIVED
NOV 23 2011
KCC WICHITA