

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-057-20758-00-00  
Spot: NENENESE Sec/Twnshp/Rge: 4-29S-22W  
2338 feet from S Section Line, 196 feet from E Section Line  
Lease Name: RICE Well #: 1-4  
County: FORD Total Vertical Depth: 5534 feet

Operator License No.: 5004  
Op Name: VINCENT OIL CORPORATION  
Address: 155 N MARKET STE 700  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	13.375	263		
11	8.625	643		WITH 475 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/29/2011 2:00 PM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: ENIDIGO Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1510' WITH 50 SX CMT. 2ND PLUG AT 670' WITH 50 SX CMT. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE  
Date/Time Plugging Completed: 10/29/2011 4:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

1ST PLUG AT 1510' WITH 50 SX CMT. 2ND PLUG AT 670' WITH 50 SX CMT. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

RECEIVED  
DEC 01 2011  
KCC WICHITA

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED

NOV 22 2011

KCC DODGE CITY

Form SP-18

12/02/11