

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21200-00-00
Spot: W2E2NE , Sec/Twnshp/Rge: 14-29S-18W
4048 feet from S Section Line, 992 feet from E Section Line
Lease Name: HOLDEMAN Well #: 1
County: KIOWA Total Vertical Depth: 4990 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3470		WITH 2 SX CMT
CIBP		4670		WITH 2 SX CMT
SURF	8.625	517		WITH 350 SX CMT
PROD	4.5	4987	0	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/11/2011 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: SHANE PELTON Company: HERMAN L. LOEB Phone: (719) 340-8987

Proposed Plugging Method: CIBP @ 4670' & 2 SX CMT. CIBP @ 3470' & 2 SX CMT. PERFORATE AT 1200' & SPOT 50 SX CMT. LET SET & TAG. FILL FROM 600' TO SURFACE.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE
Date/Time Plugging Completed: 11/11/2011 5:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

CASING WAS SQUEEZED AT 575' WITH 400 SX CMT. CMT CIRCULATED TO SURFACE ON BACKSIDE.1ST PLUG SET CIBP @ 4670' WITH 2 SX CMT. 2ND PLUG AT 3470' WITH 2 SX CMT. 3RD PLUG PERFORATE CASING AT 1200'. TIHWT TO 1200'-PUMP 50 SX CMT. WAIT ON CMT & TAG WITH TBG. 4TH PLUG 6' FILL-PULL TO 1182' & PUMP 50 SX CMT. WAIT ON CMT. TAG W/TBG. TOC @ 800'. 5TH PLUG PTT 600'. CIRCULATE CMT TO SURFACE WITH 50 SX CMT. TOP OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4726	4732		
3520	3522		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED
DEC 01 2011
KCC WICHITA

District: 01

Signed

Stephen J Pfeifer
(TECHNICIAN)

RECEIVED
NOV 18 2011
KCC DODGE CITY

Form CTS-3
12/02/11