

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-30334-00-00
Spot: S2N2SE Sec/Twnshp/Rge: 31-8S-17W
1650 feet from S Section Line, 1320 feet from E Section Line
Lease Name: DOPITA A Well #: 4
County: ROOKS Total Vertical Depth: 3399 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	143	0	125 SX
PROD	5.5	3399	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/16/2011 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: THAD STARR Company: AMERICAN ENERGIES CORPORAT Phone: (620) 793-2146

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls and ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls - 2 bags c.c. - 2 bags flocele. Casing leaks at 1100'. Casing collapsed at 1500'. Milled to 1700'. Well had multiple squeezes.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/16/2011 4:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Casing was collapsing - only got tubing to 1350'.
Swift Services rigged to tubing and pumped 70 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 675'. Swift Services rigged to tubing and pumped 205 sxs cement with 500# hulls mixed in - lost circulation.
Pulled tubing to 400' - pumped 25 sxs cement. Ran out of cement - pulled tubing.
RIH with tubing - mixed 50 sxs with 3% c.c. - 25# flocele and 150# hulls - followed with 25 sxs 60/40 pozmix - 4% gel to circulate cement to surface.
Pulled tubing. Topped off 5 1/2" casing with 5 sxs cement.
Rigged to 8 5/8" casing - pumped 25 sxs cement.
Max. P.S.I. 150#. S.I.P. 125#.

Perfs:

Top	Bot	Thru	Comments
3312	3314		
3292	3294		

RECEIVED
DEC 02 2011
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET #21134.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

NOV 21 2011

Form CP-2/3

12/02/11