

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-175-20,431-00 00  
C NE NE, SEC. 10, T. 33 S. R. 34 W/4E  
4620 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549  
Operator: Anadarko Petroleum Corporation  
Name & Address: P.O. Box 351  
Liberal, KS 67905-0351

Lease Name Hitch Unit Well # 2-1  
County Seward  
Well Total Depth 6277 204.00 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1649

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547  
Address P.O. Box 506, Liberal, KS 67905-0906

Company to plug at: Hour: 3 p.m. Day: 1 Month: 2 Year: 1994

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling Service (phone) 816-624-7455

was: 5 1/2" at 6276' w/225 sx cement, PBTD 6183', Perfs at 6152-76'

1st plug pump 1" sx hulls and 25 sx cement at perfs,

2nd plug pump 40 sx cement at 2100', 3rd plug pump 50 sx cement at 1680',

4th plug pump 35 sx cement at 650',

5th plug pump 20 sx cement at 150 to -4'.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 a.m. Day: 7 Month: 2 Year: 1994

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement at perfs, TOC 5875',

2nd plug pumped 40 sx cement at 2100',

3rd plug pumped 50 sx cement at 1680',

4th plug pumped 35 sx cement at 650',

5th plug pumped 20 sx cement at app. 150' to -4'.

Mud between all plugs.

Remarks: Used common cement by Sargent's. Recovered 2103' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

3998.2  
207

Signed Glenn R. Barlow  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 11 1994  
2-11-94  
CONSERVATION DIVISION  
Wichita, Kansas