

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-00716-00-00
Spot: SENE Sec/Twnshp/Rge: 33-16S-10W
3310 feet from S Section Line, 662 feet from E Section Line
Lease Name: SCHROEDER J Well #: 3
County: ELLSWORTH Total Vertical Depth: 3288 feet

Operator License No.: 9067
Op Name: DAMAR RESOURCES, INC.
Address: 234 W 11TH STE A PO BOX 70
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	251		200 SX
PROD	6.625	3264		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/17/2011 10:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: AVEN WEAVERLING Company: DAMAR RESOURCES, INC. Phone: (785) 623-3221

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/17/2011 12:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU-TO PULL PUMP ON OCT 21ST - COULDN'T GET OUT. LEFT 1 JOINT OF SUCKER ROD & THE PUMP IN HOLE, ALONG WITH ANCHOR CATCHER. MOVED OFF SINGLE DRUM - RIGGED UP DOUBLE DRUM - HAD TUBING PART AT 2750'. HAD WASH - OVER PIPE TO RETRIEVE TUBING - WENT DOWN TO 2990'. COULDN'T GET TUBING OUT. DUMPED 1040#S SAND ON TUBING FISH TO PRESSURE UP CASING & LOOK FOR HOLES. FOUND HOLES @ 2200-2300', & AT 400' ON UP. RUN TUBING TO 2725' & PUMPED 35 SXS COMMON CEMENT - LET SET & TAGGED @ 2495'. PERFORATED @ 1325', 1000', & 310'. RUN TUBING TO 1325' & PUMPED 35 SX'S COMMON CEMENT, PULL TUBING TO 1000' & PUMPED 35 SX'S COMMON CEMENT. PULL TUBING TO 310' & CIRCUALTE CEMENT TO SURFACE. CONNECTED ON TO BACKSIDE OF SURFACE CASING & PUMPED CEMENT TILL PRESSURED UP TO 300 #S. PULL TUBING OUT & TOP OFF.

FLUID LEVEL \approx 1,050'

Remarks: PERF TICKET #LK WIRELINE #14140. SWIFT SVC'S #21135. THIS WELL HAD BEEN WORKED ON FOR SEVERAL DAYS TO TRY & RECOVER EQUIPMENT DOWN HOLE.

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

RECEIVED

NOV 29 2011 CP-2/3

KCC WICHITA

12/06/11

1/2K