

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22376-00-01
Spot: SWNENENW Sec/Twnshp/Rge: 30-19S-6W
4866 feet from S Section Line, 3277 feet from E Section Line
Lease Name: WHITEMAN Well #: 1
County: RICE Total Vertical Depth: 3321 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	290		160 SX
T1	2.375	3100		
PROD	4.5	3307	2119	145 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/17/2011 10:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: JOE BURDETTE Company: GRESSEL OILFIELD SERVICE Phone: (620) 960-5612

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/17/2011 1:15 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, SAND PERFS TO 3190' & CAP WITH 4 SX'S CEMENT. CUT CASING OFF @ 2119' & PULL OUT OF HOLE. RUN TUBING TO 1000' & PUMP 35 SX'S COMMON CEMENT. LET SET & TAG @ 915'. PULL TUBING TO 600' & PUMP 35 SX'S COMMON CEMENT. PULL TUBING TO 340' & CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT & TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3242	3252		MISSISSIPPI

Remarks: 60-40 POZ 4% GEL - EXCEPT WHERE NOTED OTHERWISE. COPELAND C-39371

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

RECEIVED

Form CP-2/3

NOV 29 2011

12/06/11

KCC WICHITA