

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20811-00-02
Spot: NE Sec/Twnshp/Rge: 32-31S-31W
3982 feet from S Section Line, 1328 feet from E Section Line
Lease Name: ROSSON FARMS Well #: 1
County: SEWARD Total Vertical Depth: 6000 feet

Operator License No.: 6230
Op Name: FIRST NATIONAL OIL, INC.
Address: 1755 S BROADWAY ST STE 6
OVIEDO, FL 32765

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 2703 | | |
| CIBP | | 3400 | | |
| CIBP | | 5460 | | WITH 2 SX CMT |
| SURF | 8.625 | 1635 | | WITH 250 SX CMT |
| PROD | 4.5 | 5795 | 1880 | WITH 300 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/08/2011 9:30 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 5460' WITH 2 SX CMT. CIBP @ 2350' WITH 2 SX CMT. PLUG AT 1660' WITH 20 SX GEL & 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/08/2011 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5460' WITH 2 SX CMT. CIBP @ 2703'. 1ST PLUG AT 2680' WITH 300# HULLS & 40 SX CMT. 2ND PLUG AT 1645' WITH 20 SX GEL & 50 SX CMT. 3RD PLUG AT 545' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 15 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 5632 | 5634 | | |
| 5542 | 5547 | | |
| 5510 | 5516 | | |
| 2696 | 2702 | | |
| 2644 | 2654 | | |
| 2400 | 2700 | | |

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED
DEC 01 2011
KCC WICHITA

District: 01

RECEIVED

NOV 21 2011

KCC DODGE CITY

Signed

Ken Jehlik

(TECHNICIAN)

12/06/11