

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-00538-00-00
Spot: SWSWSWNE Sec/Twnshp/Rge: 10-30S-34W
2540 feet from N Section Line, 2540 feet from E Section Line
Lease Name: HUXMAN C L Well #: 2
County: HASKELL Total Vertical Depth: 2747 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA,
Address: 5205 N O CONNOR BLVD
IRVING, TX 75039

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	637		WITH 100 SX CMT
PROD 7		2528	0	WITH 125 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/08/2011 10:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RENE Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PERFORATE 7" @ 1925' & SPOT 50 SX CMT. PERFORATE 7" @ 1200' & SQUEEZE 100 SX CMT. SHUT IN & CHECK TOC. PERFORATE @ 670' & CIRCULATE TO SURFACE.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/09/2011 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

****TBG FISH @ 1940'. CASING LEAKS @ 1500'. SLOTTED LINER FROM 2563-2742'.****
1ST PLUG PERFORATE 7" @ 1925' & SPOT 50 SX CMT THROUGH TBG. TOO H. W/O CMT 2.5 HOURS. 2ND PLUG TIHWTP TO 1100'. ESTABLISH RATE PUMP 60 SX CMT. (SQUEEZE CASING LEAKS AT 1500'. TOO H.) 3RD PLUG TOC AT 1300'. PERFORATE 7" @ 652'. SDFN. 11/9/11: 4TH PLUG ESTABLISH RATE. CIRCULATED 7" X 10 3/4" ANNULUS WITH 420 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2709	2742		FT. RILEY
2664	2690		WINFIELD
2615	2649		L. KRIDER
2589	2612		U. KRIDER
2563	2576		HERRINGTON

RECEIVED
DEC 01 2011
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FLUID LEVEL** USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed _____

Ken Jehlik
(TECHNICIAN)

RECEIVED

NOV 21 2011

KCC DODGE CITY

Form CB 23

12/07/11