

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-19297-00-00
Spot: NENENW Sec/Twnshp/Rge: 10-13S-17W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: KARLIN Well #: 2
County: ELLIS Total Vertical Depth: 3544 feet

Operator License No.: 5145
Op Name: DREILING OIL INC
Address: 1008 CODY AVE PO BOX 550
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	144	0	100 SX
PROD	4.5	3544	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/22/2011 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TERRY W. PIESKER Company: DREILING OIL INC. Phone: (785) 735-4363

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.
Squeezes 955' w/175 sxs; 700' to 950' w/250 sxs; 2098' to 2552' w/200 sxs;
2330' to 2360' w/150 sxs; 2460' to 2490' w/150 sxs.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/22/2011 12:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3500' - pumped 110 sxs cement with 200# hulls.
Pulled tubing to 2100' - pumped 135 sxs cement with 200# hulls - good circulation of cement.
Pulled tubing out - tied onto backside - pumped 10 sxs cement - full.
Topped off casing with 15 sxs cement - full.

Perfs:


Top	Bot	Thru	Comments
3544	3545		
3375	3381		
3365	3367		
3289	3293		

RECEIVED
DEC 02 2011
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #34454.

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN)

CM

Form CP-2/3

12/06/11

NOV 22 2011