

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-04953-00-00
Spot: NESWNE Sec/Twnshp/Rge: 22-11S-18W
3726 feet from S Section Line, 1534 feet from E Section Line
Lease Name: HENDERSON A Well #: 2
County: ELLIS Total Vertical Depth: 3558 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3530		
SURF	8.625	262	0	150 SX
PROD	5.5	3555	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/21/2011 1:00 PM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: CURT GABEL Company: BEREXCO LLC Phone: (785) 628-6101

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/21/2011 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 750' - 1300' - 1850'.
Ran tubing to 3100' - pumped 100 sxs cement with 300# hulls.
Pulled to 2100' - pumped 110 sxs cement with 100# hulls.
Pulled to 1100' - circulated cement with 155 sxs cement and 100# hulls.
Pulled tubing - tied onto casing - pumped 75 sxs cement.
Max. P.S.I. 300#. Shut in.
Tied to surface pipe and pumped 40 sxs cement.
Max. P.S.I. 150#. Shut in.

Perfs:

Top	Bot	Thru	Comments
3307	3309		
3268	3274		
3254	3258		
3154	3160		
3136	3144		
3036	3042		
3022	3028		
3001	3008		

RECEIVED
DEC 02 2011
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #34453.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

NOV 23 2011

Form CP-2/3

12/06/11