

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05400-00-01
Spot: NENWSE Sec/Twnshp/Rge: 34-13S-20W
2252 feet from S Section Line, 1736 feet from E Section Line
Lease Name: KINGSLEY Well #: 1
County: ELLIS Total Vertical Depth: 3852 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3826		
SURF	8.625	160	0	80 SX
PROD	5.5	3842	0	125 SX

Well Type: EQR UIC Docket No: E17236.1 Date/Time to Plug: 11/15/2011 1:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KEVIN AXELSON Company: MURFIN DRILLING CO., INC. Phone: (785) 483-1314

Proposed Plugging Method: Ordered 320 sxs 60/40 pozmix - 4% gel - 500# hulls - 13 sxs gel.
Squeezes 887' w/250 sxs; 130'-160' w/250 sxs; 160' w/40 sxs.
PBTB 3826'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/15/2011 3:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perfed at 2050' - 1570'.
Murfin Drilling RIH with tubing to 3448'.
Allied rigged to tubing and pumped 5 BBL's water -
followed with 13 sxs gel - followed with 50 sxs cement and 200# hulls mixed in.
Pulled tubing to 2050'. Allied rigged to tubing and pumped 200 sxs 60/40 pozmix - 4% gel with
300# hulls mixed in to circulate cement to pit area.
Pulled tubing. Topped off 5 1/2" casing with 20 sxs - hole standing full.
8 5/8" surface casing full - visual check.

Perfs:

Top	Bot	Thru	Comments
3842	3852		ARBUCKLE
3618	3622		LANS G
3605	3610		LANS F
3598	3600		LANS F
3557	3560		LANS B
3546	3547		LANS A
3541	3543		LANS A
3533	3538		LANS A


RECEIVED
DEC 02 2011
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #34448.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

12/06/11
cc to UIC 12/05/11

NOV 21 2011