



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

January 2, 1961

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date January 2, 1961, authorized the following plugging operation:

Operator's Full Name: I. O. Miller

Complete Address: 619 Brown Bldg., Wichita, Kansas

Lease Name: Mortimer Well No. 2

Location: S/2 SW SW Sec. 33 Twp. 15 Rge. 1 (E) (W) X

County: Saline Total Depth: 2637'

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

Gun pits and circulate heavy mud. Fill hole to 200' with heavy mud. Push plug and 1/4 sack hulls to 200' and cement with 10 sacks thru drill pipe. Fill hole to 30' with heavy mud. Push plug and 1/4 sack hulls to 30' and cement with 5 sacks. Fill, bridge, and cement rathole with 2 sacks. (7" Surface pipe set at 215' cement circ.)

Very truly yours,

Signed: [Signature] Conservation Division Agent

1-10-61