



15-1169-20043-0000

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

June 29, 1970

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 18 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock,  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Art Lamb of Art Lamb Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: George Hess

Complete Address: 505 N. Charles, Mc Pherson, Kansas 67460

Lease Name: Betho Well No. 1

Location: SW NW NW Sec. 32 Twp. 15 Rge. 1 (E)(W) X

County: Saline Total Depth 2755' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Lamb was instructed to plug the well as follows:

Fill hole with sand to 2720' and cement with 5 sacks cement.

Fill hole with mud to 150'. Set reek bridge from 150' to 140' and

cement hole with 30 sacks cement. Fill hole with mud to 40'. Set reek

bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

  
Conservation Division Agent