



15:169-19054:0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date June 29, 1958, authorized the following plugging operation:

Operator's Full Name: General American Oil Co.

Complete Address: Box 352, Hutchinson, Kansas

Lease Name: Lucy Mortimer Well No. 1

Location: CS/2-S/2-SE Sec. 32 Twp. 15 Rge. 1 (E) (W)X

County: Saline Total Depth: 2649

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

Gun pits and circulate heavy mud. Fill hole with heavy mud to 170'--Push plug and 1/2 sack hulls to 170' and cement with 20 sacks thru drill pipe. Fill hole to 40' with heavy mud, push plug and 1/2 sack hulls and cement with 10 sacks.

Very truly yours,

Signed: [Signature] Conservation Division Agent

7-12-58