



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 22 1972 05-22-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Brown of Shamrock has this
date requested permission to plug the following described well:

Mr. Brown guarantees payment of the plugging fee.

Operator's full Name: Diamond Shamrock Corp.

Complete Address: Box 631, Amarillo, Texas

Lease Name: Heinson Well No. 6

Location: C SW SW SE Sec. 29 Twp. 33 Rge. 29 ~~(E)~~ (W)

County: Meade Total Depth 5983' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Brown was instructed to plug the well as follows:

13 3/8" to 958' circulated w/ cement. 7" to 5980' cemented.

Top perforations 5809' Plug bottom w/ 25 sacks cement.

Top of cement 4000' Mud 4000' to 900'

Spot 60 sacks cement 900' to 800' Mud 800' to 40'

Plug, Halls & 15 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent