

State of Kansas



15-053-19130-0090

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
APR 10 1967  
04-10-67  
CONSERVATION DIVISION  
Wichita, Kansas  
April 5, 1967

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Sam P. Wallingford

Complete Address: 304 Colorado-Derby Bldg., Wichita, Kansas

Lease Name: Gregory Well No. 1

Location: SE SE NE Sec. 26 Twp. 16 Rge. 9 (X)(W) X

County Ellsworth Total Depth 3247' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3225' and cement with 5 sacks.

Fill hole with mud to 260'. Set rock bridge from 260' to 250' and

cement hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent