



15-169-00748-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

January 17, 1961

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Handwritten notes and stamps: JAN 26 1961, CONSERVATION DIVISION, WICHITA, KANSAS

Dear Sir:

I have this date January 17, 1961, authorized the following plugging operation:

Operator's Full Name: I. O. Miller

Complete Address: 619 Brown Bldg., Wichita, Kansas

Lease Name: Mortimer Well No. 3

Location: CS/2 NW NW Sec. 4 Twp. 16 Rge. 1 (E) (W) X

County: Saline Total Depth: 2652'

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

Gun pits and circulate heavy mud. Fill hole with mud to 190'.

Push plug and hulls to 190' and cement with 10 sacks thru drill

pipe. Fill hole to 25' with mud. Push plug and hulls to 25' and

cement with 5 sacks. Bridge and cement rathole with 2 sacks.

(Surface pipe 7" set at 201' cement circulated)

Very truly yours,

Signed: [Signature] Conservation Division Agent