



15-169-20054-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

February 6, 1972

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
FEB 8 1972
CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Harry Hughes of Triangle Drilling Company has this date requested permission to plug the following described well:

Mr. Hughes guarantees payment of the plugging fee.

Operator's full Name: National Oil Company

Complete Address: 200 W. Douglas, Wichita, Kansas 67202

Lease Name: Mortimer Well No. 1

Location: ^{C SE} SE NE Sec. 5 Twp. 16 Rge. 1 (E) (W) X

County: Saline Total Depth 2678' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hughes was instructed to plug the well as follows:

Fill hole with mud to 200'. Push plug and 1/2 sack hulls to 200' and
cement hole with 25 sacks cement through drill pipe. Fill hole with
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

William J. Loman
Conservation Division Agent