

State of Kansas



15-119-30027-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

March 5, 1966

RECEIVED
STATE CORPORATION COMMISSION
MAR 10 1966
3-10-66
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bill Makely of Melland Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Makely guarantees payment of the plugging fee.

Operator's full Name: Frank J. Black

Complete Address: P.O. Box 150, Mc Pherson, Kansas

Lease Name: Larson Well No. 1

Location: NW NW SW Sec. 6 Twp. 16 Rge. 1 (E) (W) X

County Saline Total Depth 2751' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Makely was instructed to plug the well as follows:

Fill hole with mud to 130'. Push plug and 1/2 sack hulls to 130' and
cement hole with 25 sacks through drill pipe. Fill hole with mud to
30'. Push plug and 1/2 sack hulls to 30' and cap hole with 10 sacks
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent