

State of Kansas



15:169-20089-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 245 North Water
 WICHITA, KANSAS 67202
 October 6, 1978

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

J. Lewis Brock
 Administrator
 245 North Water
 Wichita, Kansas 67202

OCT 18 1978
 10-18-78
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Willard Brucker of Blackstone Drilling, Inc has this date requested permission to plug the following described well:

Mr. Brucker guarantees payment of the plugging fee.

Operator's full Name: Dale Reese Oil Company

Complete Address: 415 East Presscott, Salina, Kansas

Lease Name: Odle Well No. 1

Location: SW SE (990' WEL + 330' NSL SW 1/4)
SW SW SW 1/4 Sec. 7 Twp. 16 Rge. 1 () (W) X

County: Saline Total Depth 2730' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Brucker was instructed to plug the well as follows:

8 5/8" - 121' cement circulated. Fill hole with mud to 120'.
Push plug and 1/4 sack huls to 120' and cement
hole with 15 sacks cement. Fill hole with mud to 40'.
Push plug and 1/2 sack huls to 40' and cap hole with
10 sacks cement. Bridge rathole and cement with 2 sacks.

Very truly yours,

[Signature]
 Conservation Division Agent