

State of Kansas



15:169:00.525:0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
August 4, 1966

AUG 16 1966
8-16-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Kenneth Smith of Flint Eng. & Constr. Co. has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: George R. Hess

Complete Address: 505 N. Charles, Mc Pherson, Kansas

Lease Name: Meyer Well No. 1

Location: C N/2 SW SE Sec. 9 Twp. 16 Rge. 1 (E) (W) X

County Saline Total Depth 2664' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Smith was instructed to plug the well as follows:

Push 5 1/2" plug to 1985'. Fill hole with sand to 1975' and cement with
5 sacks. Set rock bridge from 160' to 150' and dump 25 sacks cement
on bridge. Let cement set for 12 hours. Bail hole to top of cement.
Fill hole with mud to 40'. Set rock bridge from 40' to 30' and cap
hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent