

State of Kansas



15:169:00526.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

August 2, 1966

RECEIVED  
AUG 10 1966  
8-10-66  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Kenneth Smith of Flint Eng. & Constr. Co. has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: George R. Hess

Complete Address: 505 N. Charles, McPherson, Kansas

Lease Name: Meyer Well No. 2

Location: C S/2 NW SE Sec. 9 Twp. 16 Rge. 1 (E) (W) X

County Saline Total Depth 2714' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Smith was instructed to plug the well as follows:

Fill hole with sand to 1975' and cement with 5 sacks.

Fill hole with mud to 160'. Set rock bridge from 160' to 150' and

cement hole with 25 sacks. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent