

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-1

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Saline County. Sec. 9 Twp. 16 Rge. 1 (X) (W)

Location as "NE/CNW/SW" or footage from lines. C N/2 SW SE

Lease Owner George R. Hess

Lease Name Mayer Well No. 1

Office Address 505 N. Charles McPherson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) depleted

Date well completed 7-27-63 19

Application for plugging filed 7-19-66 19

Application for plugging approved 7-21-66 19


Plugging commenced 8-3-66 19

Plugging completed 8-6-66 19

Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 2664 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 134' | none |
| | | | | 5 1/2 | 2651' | 1744' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set 10' sand bridge from 1985' to 1975' and dump 5 sacks of cement

Set 10' rock bridge from 160' to 150' and mix and dump 21 sacks of cement

Let cement set over night

Bail hole down to cement and dump 4 sacks of dry cement

Mud hole to 40' and dump 10 sacks of cement to surface

Handwritten notes and stamps: AUG 12 1966, 8-12-66, and other illegible markings.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Flint Engineering and Construction Co.
Address 2375 W. Central El Dorado, Kansas

STATE OF Kansas COUNTY OF Butler ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) *Jeanne Davis*

(Address)

SUBSCRIBED AND SWORN TO before me this 10 day of August, 1966

My commission expires Sept. 27, 1967

Ronald P. Hanson
Notary Public.



15-169-00525-0000

Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON • KANSAS

July 29, 1963

COMPANY: GEORGE R. NESS
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: MAYER #1
 LOCATION: C-N/2 SW/4 SE/4, Sec. 9-16-1
 Saline County, Kansas
 COMMENCED: July 19, 1963
 COMPLETED: July 27, 1963
 ELEVATION: 1289 K. B.

| | | | |
|------|----|------|----------------|
| 0 | to | 45 | Sandy Shale |
| 45 | to | 134 | Shale & Shells |
| 134 | to | 240 | Lime |
| 240 | to | 490 | Lime & Shale |
| 490 | to | 665 | Lime |
| 665 | to | 860 | Lime & Shale |
| 860 | to | 1380 | Shale & Lime |
| 1380 | to | 1655 | Lime & Shale |
| 1655 | to | 1795 | Lime |
| 1795 | to | 1863 | Lime & Shale |
| 1863 | to | 1940 | Sand & Shale |
| 1940 | to | 2010 | Lime & Shale |
| 2010 | to | 2395 | Lime |
| 2395 | to | 2485 | Lime & Shale |
| 2485 | to | 2664 | Shale & Lime |
| | | 2664 | T. D. |

RECORDED
 AUG 12 1963
 MISSOURI DIVISION
 SALINE COUNTY, KANSAS

Cut 12 1/4 in. hole to 134 ft. and run 135 ft. of 8 5/8 in. O.D. casing and cemented on bottom at 134 ft. with 100 sacks cement and 3 sacks calcium chloride. Cut 7 7/8 in. hole to 2664 ft. and run 2672.67 ft. of 5 1/2 in. pipe and cemented with 150 sacks cement and 2 1/2 Gal. 12 1/2 ft. off bottom at 2651.50 ft. One piece shoe. Cement pumped to plug. Plug down at 4:30 P.M., July 27, 1963.

TOPS: Brown Line - 1943' Kansas City - 1986' Mississippi - 2649'

Measurements taken from K. B.

CERTIFICATE

I, H. J. Plouffe, president of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Mayer #1 located in the C-N/2 SW/4 SE/4 of Sec. 9-16-1, Saline County, Kansas as reflected by files of the Blackstone Drilling, Inc.

H. J. Plouffe
 H. J. Plouffe - President

Subscribed and sworn to before me a Notary Public within and for McPherson County, Kansas this 30th day of July, 1963.

Ruth McVay
 Ruth McVay - Notary Public

My Commission Expires: 12/18/65