


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-169-20081-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Saline County. Sec. 8 Twp. 16 Rge. I W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines _____
NW/ NW/ SE
Lease Owner Dick Hess
Lease Name Stanley Bickel Well No. I
Office Address 1414 Dover Rd. McPherson, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) Oil



Locate well correctly on above
Section Plot

Date Well completed 9-24 1977
Application for plugging filed 3-27 1978
Application for plugging approved 3-28 1978
Plugging commenced 3-29 1978
Plugging completed 4-6-12 1978
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2698'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4"		2025'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Plugged off bottom of hole with sand. Sand from 2698' to 2650'. Dumped 5 sx of cement; 3 sx Hulls 15 sx Gel; 1 sx Hulls; 75 sx cement. Pump Pressure 150 #

RECEIVED
APR 11 1978
4-14-78
CLERK OF COURSE
McPherson, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Inc.
2809 King - Hutchinson, Kansas 67501

STATE OF Kansas COUNTY OF Reno, ss.
Connie Fletcher (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Connie Fletcher
511 West 18th Hutchinson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of April, 1978

Connie Campbell
Notary Public.

My commission expires July 6th, 1981

CONNIE CAMPBELL
STATE NOTARY PUBLIC
RENO COUNTY, KANSAS
MY APPT. EXP. 7-6-81



15-169-20081-0000

Blackstone Drilling, Inc.

Box 1284 • 523 West Kansas • Phone (316) 241-1250
McPHERSON, KANSAS 67460

September 26, 1977

COMPANY: DICK RESS

CONTRACTOR: BLACKSTONE DRILLING, INC.

FARM: STANLEY BICKEL #1

LOCATION: NW NW SE Sec. 8-16-1W,
Saline County, Kansas

COMMENCED: September 17, 1977

COMPLETED: September 24, 1977

ELEVATION:

0	to	40	Shale & Lime
40	to	110	Blue Shale
110	to	625	Lime & Shale
625	to	825	Shale
825	to	1105	Lime & Shale
1105	to	1680	Shale
1680	to	1845	Lime
1845	to	2060	Shale & Lime
2060	to	2628	Lime
2628	to	2679	Shale
2679	to	2698	Mississippi T. S.

Out 12 1/2" hole to 110' and run 112' of 8 5/8" pipe, cemented with 100 sacks of cement at 110'. Plug down at 11:30 A. M., September 17, 1977. Out 7 7/8" hole to 2698'. Run 5" pipe, cemented 5' off bottom with 35 sacks of cement at 2693'. Plug down at 8:00 A. M., September 24, 1977.

TOPS: MISSISSIPPI - 2679'

Measurements taken from K. H.


CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Stanley Bickel #1, located on the NW NW SE Sec. 8-16-1W, Saline County, Kansas as reflected by the files of Blackstone Drilling, Inc.


P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 26th day of September, 1977.


Johnnie L. Schmidt - Notary Public

 JOHNIE L. SCHMIDT
McPherson County, Kansas
My Appl. Exp. June 23, 1981