


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Saline County. Sec. 8 Twp. 16 Rge. 1 W. (E) (W)
Location as "NE/CNW/SW" or footage from line N/2 NW SE
Lease Owner Molland Drilling Co.
Lease Name Ivan Henna Well No. I
Office Address Br 783 Mc Pherson, Kansas 67460
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 3-26 1965
Application for plugging filed 12-20 1969
Application for plugging approved 12-21 1969
Plugging commenced 12-23 1969
Plugging completed 12-24 1969
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2688' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	PUT IN	PULLED OUT
		STATE CORPORATION COMMISSION	51"		2,361'
		DEC 29 1969			
		CONSERVATION DIVISION			
		Wichita, Kansas			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged ~~###~~ off bottom of hole with sand. Sand from 2688' to 2650'. Dumped 5 sx of cement. Mudded hole to 160'. Made 10' of rock bridge. Dumped 30 sx of cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 sx of cement, ~~###~~ filling to the bottom of the collar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb2809 King St. Hutchinson, Kansas 67501
(Address)SUBSCRIBED AND SWORN to before me this 26th day of December 19 69My commission expires January 5, 1970

Notary Public.

WELL RECORD

LEASE: Ivan Henne

WELL NO. 1

ELEVATION: 1330 RB
145LOCATION: N/2 NW SE
Sec. 8-16-14

COMMENCED: 3/20/65

COMPLETED: 3/26/65

OPERATOR: F. S. Williams

CONTRACTOR: Melland Drilling Company, Inc.
Post Office Box 783
McPherson, KansasCASING RECORD: 8 5/8" @ 130'/90ax
5 1/2" @ 2065'/50ax
2665'

FORMATION	LOG
shale & shells	130
lime & shale	805
shale	1219
shale & shells	1520
shale & lime	1765
lime & shale	2000
shale	2045
lime & shale	2410
shale & shells	2688
RTD	2688

FORMATION LOG

CERTIFICATE

State of Kansas, County of McPherson, ss.

I, **Donald J. Melland**, do hereby certify that the above is a true and correct copy of the log of the above named and described well, as reflected by the records of the Melland Drilling Company, Inc.

Subscribed and sworn to before me, a Notary Public, in and for the County of McPherson, State of Kansas,

this 31st day of March 19 65.

My Commission expires: May 7, 1968

Notary Public