

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 8914
Name: H & C Oil Operating, Inc.
Address 1: P.O. Box 86
Address 2: _____
City: Plainville State: KS Zip: 67663 + 0086
Contact Person: Charles R. Ramsey
Phone: (785) 434-7434
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
None Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 135-25,298-00-00
Spot Description: _____
SE SW NE NW Sec. 32 Twp. 17 S. R. 26 East West
1,130 Feet from North / South Line of Section
1,930 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ness
Lease Name: Solze Well #: 32-1
Date Well Completed: 10/9/2011
The plugging proposal was approved on: 10/5/2011 (Date)
by: Eric MacLaren (KCC District Agent's Name)
Plugging Commenced: 10:00PM 10/8/2011
Plugging Completed: 12:30AM 10/9/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface Pipe	8 5/8	265	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

(1st Plug @ 1950'W/50sks)(2nd Plug @ 1110'W/80sks)(3rd Plug @ 510'W/40sks)(4th Plug @ 300'W/50sks)(5th Plug @ 60'W/20sks)(30sks In Rat Hole)(20sks In Mouse Hole)(Total 290sks60/40Poz 4%Gel W/1/4#CF/sk By Quality Oilwell Cementing)(Completed @ 12:30AM 10/9/2011)(Circulated 1st Plug 15 Minutes W/58 Vis MUD)(Plugs displaced with MUD)

RECEIVED
NOV 23 2011

Plugging Contractor License #: 31548 Name: Discovery Drilling Co., Inc. **KCC WICHITA**
Address 1: P.O. Box 763 Address 2: 1029 Reservation Road
City: Hays State: Kansas Zip: 67601 + 0763
Phone: (785) 623-2920

Name of Party Responsible for Plugging Fees: H & C Oil Operating, Inc.
State of KANSAS County: ROOKS, ss. CHARLES R. RAMSAY Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Charles R. Ramsey

AK