

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 4058 Name: American Warrior Inc. Address 1: P.O. Box 399 Address 2: City: Garden City State: Ks Zip: 67846 Contact Person: Jody Smith Phone: (620) 275-2963 Type of Well: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): Arbuckle Depth to Top: 3865' Bottom: 3874' T.D. 3882'

API No. 15 - 051-22937 . 00 . 00 Spot Description: C NW SE NE Sec. 1 Twp. 14 S. R. 20 East West 3040 3637 Feet from North South Line of Section 1250 1245 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Ellis Lease Name: Hertel Well #: A-2 Date Well Completed: 5/15/82 The plugging proposal was approved on: 11/7/11 by: Pat Staab Plugging Commenced: 11/21/11 Plugging Completed: 11/21/11

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Casing, Size, Setting Depth, Pulled Out). Row 1: Arbuckle, oil, surface, 85/8, 250', 0. Row 2: Production, 51/2, 3883', 0.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Log Tech perf 2050', 1555' and 800', 2spf. Ran tbg to 3700'. Swift hooked up to tbg, Mixed and pumped 150sx 60/40 poz 4% gel w/300# hulls, Pulled tbg to 2400', Swift hooked up to tbg, Mixed and pumped 120sx 60/40 poz w/ 100# hulls. Pulled tbg to 1200'. Swift hooked up to tbg, Mixed and pumped 120sx 60/40 poz w/100# hulls, Cement circulated to surface. Pulled tbg. Swift hooked up to 85/8 Mixed and pumped 10sx 60/40 poz 4% gel. Swift topped 51/2 off with 25sx 60/40 poz 4% gel.

Plugging Contractor License #: 32382 Name: Swift Services, Inc. Address 1: P.O. Box 466 Address 2: City: Ness City State: Ks Zip: 67560 Phone: (785) 798-2300 Name of Party Responsible for Plugging Fees: American Warrior Inc. State of Kansas County, Finney Jody Smith Employee of Operator or Operator on above-described well

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Handwritten Signature]

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED NOV 23 2011 KCC WICHITA



CHARGE TO: **AMERICAN WARRIOR Inc**
 ADDRESS:
 CITY, STATE, ZIP CODE:

RECEIVED
 NOV 23 2011
 KCC WICHITA

TICKET No 21137

PAGE 1 OF 1

SERVICE LOCATIONS 1. HAYS	WELL/PROJECT NO. A-2	LEASE HERTEL	COUNTY/PARISH ELLIS	STATE KS	CITY	DATE 11-21-11	OWNER
2. NESS	TICKET TYPE <input checked="" type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR	RIG NAME/NO. EXPRESS JEL	SHIPPED VIA GT	DELIVERED TO YOCUMENT	ORDER NO.	
3.	WELL TYPE OIL	WELL CATEGORY ABANDON	JOB PURPOSE PTA	WELL PERMIT NO.	WELL LOCATION		
4. REFERRAL LOCATION	INVOICE INSTRUCTIONS						

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		UNIT		UNIT PRICE	AMOUNT	
		LOC	ACCT	OF								
575		1			MILEAGE 4/112	30	mi			6.00	180	00
576-P		1			Pump Service	1	ea			1000.00	1000	00
075		1			COTTEN SELL HALLS	7	SH			25.00	175	00
090		1			D-AM	4	GR			35.00	140	00
328-4		2			60-10 4 1/2 GEL	405	SK			11.50	4887	50
581		2			SERVICE CHG GWT	475	SK			2.00	950	00
583		2			DRAYAGE	597.79	TR			1.00	597	79

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X **JOE SMITH** [Signature]
 DATE SIGNED: **11-21-11** TIME SIGNED: **1:30** A.M. P.M.

REMIT PAYMENT TO:
SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	7930.29
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?					
WE UNDERSTOOD AND MET YOUR NEEDS?					
OUR SERVICE WAS PERFORMED WITHOUT DELAY?					
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TAX	
ARE YOU SATISFIED WITH OUR SERVICE?	<input type="checkbox"/> YES	<input type="checkbox"/> NO		TOTAL	
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND					

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR: **[Signature]** APPROVAL: _____

Thank You!

11/22/2011 03:07 swift services (FAX) P.001/001

JOB LOG

SWIFT Services, Inc.

DATE 11-21-11 PAGE NO. 1

CUSTOMER AWI WELL NO. A-2 LEASE HORTEL JOB TYPE PYA TICKET NO. 21137

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL/HR)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CABING	
	1330							ONLOCATION CMT: 425SG 60-40 psi 4 1/2" OREL 500' HALLS 2 3/8" x 5 1/2" 20-3282, 2 5/8" 250
	1415	3.5	5.0	✓		600		T36 @ 3771, MIX 1525SG 4 1/2" 300' HALLS START H2O
			0	✓				" CMT
			12.0	✓				CIRC WATER
			39.0	✓				END CMT
	1430		5.0	✓				H2O PULL T36 UP TO 2700', MIX 1025SG 4 1/2" 100' HALLS
	1500	3.5	0	-		500		START CMT
			6.0	-				CIRC WATER
			31.0	-				END CMT
	1520		3.0	-				Disp PULL T36 UP TO H2O', MIX 625SG 4 1/2" 100' HALLS
	1540	3.5	0	-		400		START CMT
			5.0	-				CIRC WATER
			30.0	-				CIRC CMT!!
	1550		31.0	-				END PULL T36 OUT!
	1625		2.5	-		200		2 5/8" MIX 1225SG
	1640		7.0	-				TOP OFF 5 1/2" OREL 2525SG CMT DOWN 15 FT
	1730							TOTAL CMT: 425SG JOB COMPLETE " HALLS = 500'
								THANK YOU! DAVE JOSEPH, LANE

RECEIVED

NOV 23 2011

KCC WICHITA